



ADDENDUM NO.1

ATTENTION: ALL BIDDERS

DATE: 23/04/2025

BID NO: 40-2024-2025T

PROJECT TITLE: REPAIRING OF 4.5KM GRAVEL ROADS AND STORMWATER CHANNELS IN WARD 9: JOVELENI, HINANA AND VOYIZANA

1. Issue Addenda

Clause C 3.2 of the Standard Conditions of Tender states "If necessary, issue addenda in writing that may amend or amplify the tender documents to each tenderer during the period from the date the tender documents are available until one week before the tender closing time stated in the Tender Data. The Employer reserves its rights to issue addenda less than one week before the tender closing time in exceptional circumstances.

Notwithstanding any requests for confirmation of receipt of Addenda issued, the tenderer shall be deemed to have received such addenda if the employer can show proof of transmission thereof (or a notice in respect thereof) via electronic mail, facsimile or registered post."

YOU ARE HEREBY ADVISED OF THE FOLLOWING CLARITY/CHANGES

13.01 (c) Time related obligations unit changed to 'Month'

15.03 (J) 450mm traffic cones

22.03 Concrete pipe culvert class clarifies as Class 100D

34.01 Description changed to 'Extra over item 34.01 for adding extra material'

The revised PAGE indicating the above-mentioned changes is attached to the addendum.

Compiled By Senqu PMU: Mr N. Nkopane

Approved By Senqu SCM: Mr N Ngwenya



ADDENDUM NO.1

ATTENTION: ALL BIDDERS

DATE: 23/04/2025

BID NO: 40-2024-2025T

**PROJECT TITLE: REPAIRING OF 4.5KM GRAVEL ROADS AND STORMWATER CHANNELS IN WARD
9: JOVELENI, HINANA AND VOYIZANA**

I, the below signatory herewith acknowledges the receipt of the addenda that was issued on the 23th of April 2025

Name of Entity: _____

Bidder's Representative Name: _____

Bidder's Representative Signature: _____

Signature Date: _____

Please sign this document and send back to Senqu SCM to the provided contact information in the Tender Data, upon receipt of the addendum.

SENQU LOCAL MUNICIPALITY

REPAIRING OF 4.5KM GRAVEL ROADS AND STORMWATER CHANNELS IN WARD 9: JOVELENI, HINANA AND VOYZANA

1300 : CONTRACTOR'S ESTABLISHMENT ON SITE AND GENERAL OBLIGATIONS

ITEM NO.	PAYMENT CLAUSE	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
13.01	COLTO 1300	SECTION 1300 : CONTRACTOR'S ESTABLISHMENT ON SITE AND GENERAL OBLIGATIONS				
		(a) Fixed obligations	Sum	1.00		
		(b) Value-related obligations	Sum	1.00		
		(c) Time-related obligations	Month	6.00		
TOTAL AMOUNT OF SECTION 1300 CARRIED FORWARD TO SUMMARY OF SCHEDULES						

SENQU LOCAL MUNICIPALITY

REPAIRING OF 4.5KM GRAVEL ROADS AND STORMWATER CHANNELS IN WARD 9: JOVELENI, HINANA AND VOYZANA

1500: ACCOMMODATION OF TRAFFIC

ITEM NO.	PAYMENT CLAUSE	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	COLTO 1500	ACCOMMODATION OF TRAFFIC				
15.01		Accommodating traffic and maintaining temporary deviations	km	4.50		
15.02		<u>Earthworks for temporary deviations:</u>				
		(a) Shaping of temporary deviations	km	4.50		
15.03		<u>Temporary traffic-control facilities:</u>				
		(a) Flagmen	man-day	252.00		
		(b) Portable STOP and GO-RY signs	no.	8.00		
		(c) Temporary traffic-control signals as specified or as shown on drawings	no.	8.00		
		(d) Amber flicker lights	no.	8.00		
		(e) Road signs, R- and TR-series (size indicated)	no.	8.00		
		(f) Road signs, TW-series (size indicated)	no.	8.00		
		(g) Road signs, STW-, DTG-, TGS-, AND TG-series (excluding delineators and barricades)	no.	8.00		
		(h) Delineators (DTG50J) (size indicated):				
		(i) Single	no.	15.00		
		(ii) Mounted back to back	no.	25.00		
		(i) Movable barricade/road sign combination (size indicated)	no.	5.00		
		(j) 450mm Traffic cones	no.	20.00		
TOTAL AMOUNT OF SECTION 1500 CARRIED FORWARD TO SUMMARY OF SCHEDULES						

SENQU LOCAL MUNICIPALITY

REPAIRING OF 4.5KM GRAVEL ROADS AND STORMWATER CHANNELS IN WARD 9: JOVELENI, HINANA AND VOYZANA

2200: PREFABRICATED CULVERTS

ITEM NO.	PAYMENT CLAUSE	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
22.01	COLTO 2200	PREFABRICATED CULVERTS <u>Excavation:</u> (a) Excavating soft material situated within the following depth ranges below the surface level: (i) 0 m up to 1.5 m (ii) Exceeding 1.5 m and up to 3.0 m (iii) Etc, in increments of 1.5 m (b) Extra over subitem 22.01(a) for excavation in hard material, irrespective of depth				
			m³	47.25		
			m³	94.50		
			m³	Rate Only		Rate Only
22.02		<u>Backfilling:</u> (a) Using the excavated material (b) Extra over subitems 22.02(a) and (b) for soil cement backfilling (8% cement)				
			m³	141.75		
			m³	130.41		
22.03		<u>Concrete pipe culverts (Class 100D):</u> (a) On class A bedding (450mm diameter) (a) On class A bedding (600mm diameter) (a) On class A bedding (750mm diameter) (a) On class A bedding (900mm diameter) (a) Without prefabricated floor slabs (1800mm x 1800mm RP-75S) (b) Without prefabricated floor slabs (3000mm x 3000mm RP-75S) (a) Mild steel bars (b) High-tensile steel bars (c) Welded steel fabric				
			m	50.00		
			m	Rate Only		Rate Only
			m	Rate Only		Rate Only
			m	Rate Only		Rate Only
			m	Rate Only		Rate Only
			m	Rate Only		Rate Only
			t	Rate only		Rate Only
			t	Rate Only		Rate Only
			kg	100.00		
22.04		<u>Brickwork</u> (a) 115 mm thick (b) 230 mm thick				
			m²	Rate Only		Rate Only
			m²	48.00		
TOTAL AMOUNT OF SECTION 2200 CARRIED FORWARD TO SUMMARY OF SCHEDULES						

SENQU LOCAL MUNICIPALITY

REPAIRING OF 4.5KM GRAVEL ROADS AND STORMWATER CHANNELS IN WARD 9: JOVELENI, HINANA AND VOYZANA

3400: PAVEMENT LAYERS OF GRAVEL MATERIAL

ITEM NO.	PAYMENT CLAUSE	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
34.01	COLTO 3400	PAVEMENT LAYERS OF GRAVEL MATERIAL				
		<u>Pavement layers constructed from gravel taken from cut or borrow, including free-haul up to 10km:</u>				
		(a) Gravel selected G7 layer compacted to 93 % of modified AASHTO density, using:				
		(i) Non-cemented material (150mm thick layer)	m ³	3375.00		
		(b) Gravel subbase G6 (unstabilized material) compacted to 95 % of modified AASHTO density, using:				
		(i) Non-cemented material (150mm thick layer)	m ³	3375.00		
		(c) Gravel base (chemically stabilized material) compacted to 95 % of modified AASHTO density, using:				
		(i) Non-cemented material (150mm thick layer)	m ³	Rate Only		Rate Only
		<u>Extra over item 34.01 for adding extra material</u>				
		(a) Gravel shoulder wearing course	m ³	405.00		
		(b) Dump rock	m ³	Rate Only		Rate Only
TOTAL AMOUNT OF SECTION 3400 CARRIED FORWARD TO SUMMARY OF SCHEDULES						